

CEMENT DISPENSER RANGE

Thanks for the opportunity to submit prices and specs for our cement dispenser range.

Non deductive weighing dispensers

Our units are of heavy duty construction to withstand site conditions. They are comprised of either a one or two tonne capacity bin and a high output screw conveyor

Technical Features:

- Variable pitch flights to prevent choking
- 168mm screw conveyor output 17t/hr
- Weatherproof plastic cover
- 5m Auger support & sock
- Oil Immersed Gear box
- Manual stop/start
- Sturdy frame
- Bag Breaker

1t Dispenser, standard frame, manual on/off (no weighing) \$16,580.00 + GST

2t Dispenser, standard frame, manual on/off (no weighing) \$18,090.00 + GST

1t Dispenser with mobile frame, manual on/off (no Weighing) \$20,580.00 + GST

2tDispenser with mobile frame, manual on/off (no Weighing) \$22,750.00 + GST



1t manual non-deductive weighing dispenser – standard frame

Note: Unit shown may vary visually from unit manufactured and delivered.

Deductive weighing cement and powder dispenser

Designed to dispense cement easily from bulk bags, with minimal dust pollution. A range of sizes are offered in either manual or electronic configurations. A deductive weighing system allowing preset amounts to be programmed into the controller for fuss free dispensing is as quoted below.

Technical Features:

- 1t and 2t capacity bins.
- 219mm screw conveyor output 35 to 40t/hr.
- Screw Auger dump height 4200mm
- Electronic load cells with deductive weighing.
- 5m Auger support & sock
- Sturdy frame. Access ladder. Weatherproof plastic cover. Bag Breaker.

1t Dispenser with de-cumulative weigh system: \$32,175.00 + GST

2t Dispenser with de-cumulative weigh system: \$33,475.00 + GST

Note: Both with Mobile frame



1t De-Cumulative Cement Dispenser- mobile frame

Note: Unit shown may vary visually from unit manufactured and delivered.

Optional Equipment (available for all silo types)

Dust suppression/loading cone (Excluding Vacuum unit)	\$4,100.00 + GST
Vibrator	\$240.00 + GST

Delivery:

Allow 10 to 12 weeks from date of order confirmation and deposit not including Festive or vocational holidays.

Warranty:

12 months after delivery for the mechanical parts (excluding normal wear). 6 months after delivery for electric and electronic parts (excluding normal wear). The warranty covers materials and does not include their shipping and the labor needed for their replacement.

Additional Items not included in quote:

GST

Commissioning costs – \$135.00/hour

Earthworks

Accommodation, board and lodging for our technician(s)

Running electrical and water mains to the plant

Any modifications and/or extra work demanded by you on site to the plant or installation.

Loading ramp(s) or concrete buttresses as or if required

Crane hire, equipment hire for lifting or special tools and equipment.

Terms of payment:

A non refundable deposit of 20% with order, and balance prior to dispatch from manufacturer's factory or our works is required, for purchase.

Validity:

The prices shown are valid for 30 days from submission, following which, we reserve the right to confirm or re-quote.

Please do not hesitate to contact me if you require any additional information.

Tony Cammarano
Batchcrete International Pty Ltd
0400 121 308
tonycam@batchcrete.com.au